

Report Date: May 10, 2021

Project: Virgil E Brown

Inspector(s): Julie Gue, Certified Technician

Inspection and Test Date(s):

- October 22, 2020 – January 20, 2021

Duct Fabricators, Inc. "Fire Safety Division" inspected Two hundred and fifty-six fire dampers for proper installation. The dampers were then tested and photographed in the "open" and "closed" positions to confirm that they were functioning as designed.

All fire dampers have passed both visual and functional testing.

NOTES: NFPA 80, NFPA 101 and NFPA 105 require newly installed dampers to be inspected and tested one year after initial installation. Thereafter, dampers are to be visually inspected every two years and functionally tested every four years.

Additionally, the information contained herein verified whether the dampers were functional at the time of testing. This verification process does not represent any form of a guarantee that the dampers will properly perform in the future.

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
1	FD	AHU1.1-S1	56x16	Ruskin	IBD2	Pass	Pass	None
2	FD	AHU1.1-S2	56x16	Ruskin	IBD2	Pass	Pass	None
3	FD	AHU1.1-S3	8x10	Ruskin	IBD2	Pass	Pass	None
4	FD	AHU1.1-S4	8x10	Ruskin	IBD2	Pass	Pass	New Damper Installed
5	FD	AHU1.1-S5	11x8 Oval	Ruskin	IBD2	Pass	Pass	None
6	FD	AHU1.1-S6	56x16	Ruskin	IBD2	Pass	Pass	Added screws to angle
7	FD	AHU1.1-S7	56x16	Ruskin	IBD2	Pass	Pass	Added screws to angle
8	FD	AHU1.1-S8	6" round	Ruskin	IBD2	Pass	Pass	None
9	FD	AHU1.1-S9	56x16	Ruskin	IBD2	Pass	Pass	Added screws to angle
10	FD	AHU1.1-S10	8x10	Ruskin	IBD2	Pass	Pass	None
11	FD	AHU1.1-S11	56x16	Ruskin	IBD2	Pass	Pass	Added screws to angle
12	FD	AHU1.1-OA	96x24	Ruskin	IBD2	Pass	Pass	None
13	FD	AHU1.1-RA	96x60	Ruskin	IBD2	Pass	Pass	None
14	FD	AHU1.2-S1	36x8	Ruskin	IBD2	Pass	Pass	None
15	FD	AHU1.2-S2	36x8	Ruskin	IBD2	Pass	Pass	None
16	FD	AHU1.2-S3	56x16	Ruskin	IBD2	Pass	Pass	Added screws to angle
17	FD	AHU1.2-S4	56x16	Ruskin	IBD2	Pass	Pass	Added screws to angle
18	FD	AHU1.2-S5	8x10	Ruskin	IBD2	Pass	Pass	None
19	FD	AHU1.2-S6	17x8 oval	Ruskin	IBD2	Pass	Pass	None
20	FD	AHU1.2-S7	17x8 oval	Ruskin	IBD2	Pass	Pass	None

Inspector: Julie Gue
Inspection Dates: October 22, 2020 -January 20, 2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
37	FD	AHU2.1-S1	56x16	Ruskin	IBD2	Pass	Pass	added screws
38	FD	AHU2.1-S2	12" oval	Ruskin	IBD2	Pass	Pass	None
39	FD	AHU2.1-S3	56x16	Ruskin	IBD2	Pass	Pass	None
40	FD	AHU2.1-S4	8x10	Ruskin	IBD2	Pass	Pass	Added screws
41	FD	AHU2.1-S5	6"round	Ruskin	IBD2	Pass	Pass	None
42	FD	AHU2.1-S6	20x8 oval	Ruskin	IBD2	Pass	Pass	None
43	FD	AHU2.1-S7	28x10	Ruskin	IBD2	Pass	Pass	None
44	FD	AHU2.1-S8	6" Round	Ruskin	IBD2	Pass	Pass	None
45	FD	AHU2.1-S9	10" Round	Ruskin	IBD2	Pass	Pass	None
46	FD	AHU2.1-S10	8" Round	Ruskin	IBD2	Pass	Pass	None
47	FD	AHU2.1-S11	34x19	Ruskin	IBD2	Pass	Pass	None
48	FD	AHU2.1-S12	20x8 oval	Ruskin	IBD2	Pass	Pass	None
49	FD	AHU2.1-S13	6" Round	Ruskin	IBD2	Pass	Pass	None
50	FD	AHU2.1-S14	56x16	Ruskin	IBD2	Pass	Pass	Added screws
51	FD	AHU2.1-S15	8x10	Ruskin	IBD2	Pass	Pass	None
52	FD	AHU2.1-S16	56x16	Ruskin	IBD2	Pass	Pass	Added Screws
53	FD	AHU2.1-OA	96x24	Ruskin	IBD2	Pass	Pass	Added screws/ larger angle
54	FD	AHU2.1-RA	96x60	Ruskin	IBD2	Pass	Pass	Added screws/ larger angle
55	FD	AHU2.2-S1	38x8	Ruskin	IBD2OW	Pass	Pass	None
56	FD	AHU2.2-S2	38x8	Ruskin	IBD2OW	Pass	Pass	None

Inspector: Julie Gue
Inspection Dates: Octobr 22, 2020 -January 20, 2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
57	FD	AHU2.2-S3	56x16	Ruskin	IBD2	Pass	Pass	Added more screws
58	FD	AHU2.2-S4	56x16	Ruskin	IBD2	Pass	Pass	Added more screws
59	FD	AHU2.2-S5	8x10	Ruskin	IBD2	Pass	Pass	Curtain moved further into wall
60	FD	AHU2.2-S6	6" Round	Ruskin	IBD2	Pass	Pass	None
61	FD	AHU2.2-S7	16" Oval	Ruskin	IBD2	Pass	Pass	None
62	FD	AHU2.2-S8	6" Round	Ruskin	IBD2	Pass	Pass	None
63	FD	AHU2.2-S9	32x10	Ruskin	IBD2	Pass	Pass	Added screws to retaining angle
64	FD	AHU2.2-S10	12" Round	Ruskin	IBD2	Pass	Pass	None
65	FD	AHU2.2-S11	12" Oval	Ruskin	IBD2	Pass	Pass	None
66	FD	AHU2.2-S12	34x10	Ruskin	IBD2	Pass	Pass	None
67	FD	AHU2.2-S13	6" Round	Ruskin	IBD2	Pass	Pass	None
68	FD	AHU2.2-S14	6" Round	Ruskin	IBD2	Pass	Pass	none
69	FD	AHU2.2-S15	56x16	Ruskin	IBD2	Pass	Pass	Added screws to retaining angle
70	FD	AHU2.2-S16	8x10	Ruskin	IBD2	Pass	Pass	None
71	FD	AHU2.2-S17	56x16	Ruskin	IBD2	Pass	Pass	Added screws to retaining angle
72	FD	AHU2.2-S18	18x10	Ruskin	IBD2	Pass	Pass	Anchors added
73	FD	AHU2.2-OA	96x24	Ruskin	IBD2	Pass	Pass	None
74	FD	AHU2.2-RA	96x60	Ruskin	IBD2	Pass	Pass	None

Inspector: Julie Gue
Inspection Dates: October 22, 2020 - January 20, 2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
75	FD	AHU3.1-S1	56x16	Ruskin	IBD2	Pass	Pass	screws added
76	FD	AHU3.1-S2	56x16	Ruskin	IBD2	Pass	Pass	screws added
77	FD	AHU3.1-S3	56x16	Ruskin	IBD2	Pass	Pass	screws added
78	FD	AHU3.1-S4	8"Round	Ruskin	IBD2	Pass	Pass	None
79	FD	AHU3.1-S5	40x12	Ruskin	IBD2	Pass	Pass	None
80	FD	AHU3.1-S6	56x12	Ruskin	IBD2	Pass	Pass	screws added
81	FD	AHU3.1-S7	56x16	Ruskin	IBD2	Pass	Pass	None
82	FD	AHU3.1-S8	20x10	Ruskin	IBD2	Pass	Pass	None
83	FD	AHU3.1-S9	16" oval	Ruskin	IBD2	Pass	Pass	None
84	FD	AHU3.1-S10	6" Round	Ruskin	IBD2	Pass	Pass	None
85	FD	AHU3.1-S11	56x16	Ruskin	IBD2	Pass	Pass	screws added
86	FD	AHU3.1-S12	8x10	Ruskin	IBD2	Pass	Pass	None
87	FD	AHU3.1-S13	56x16	Ruskin	IBD2	Pass	Pass	screws added
88	FD	AHU3.1-S14	20x10	Ruskin	IBD2	Pass	Pass	None
89	FD	AHU3.1-OA	96x24	Ruskin	IBD2	Pass	Pass	Installed larger angle
90	FD	AHU3.1-RA	96x60	Ruskin	IBD2	Pass	Pass	Installed larger angle
91	FD	AHU3.2-S1	36x8	Ruskin	IBD2OW	Pass	Pass	None
92	FD	AHU3.2-S2	36x8	Ruskin	IBD2OW	Pass	Pass	None
93	FD	AHU3.2-S3	56x16	Ruskin	IBD2	Pass	Pass	screws added
94	FD	AHU3.2-S4	56x16	Ruskin	IBD2	Pass	Pass	screws added

Inspector:

Julie Gue

SA = Supply Air

FD = Fire Damper

Inspection Dates:

October 22, 2020 - January 20, 2021

RA = Relief Air

EF = Exhaust Fan

Facility:

Virgil E Brown

OA = Outside Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
95	FD	AHU3.2-S5	8x10	Ruskin	IBD2	Pass	Pass	None
96	FD	AHU3.2-S6	14x8 Oval	Ruskin	IBD2	Pass	Pass	None
97	FD	AHU3.2-S7	6" Round	Ruskin	IBD2	Pass	Pass	None
98	FD	AHU3.2-S8	56x16	Ruskin	IBD2	Pass	Pass	screws added
99	FD	AHU3.2-S9	56x16	Ruskin	IBD2	Pass	Pass	screws added
100	FD	AHU3.2-S10	56x16	Ruskin	IBD2	Pass	Pass	screws added
101	FD	AHU3.2-S11	6" Round	Ruskin	IBD2	Pass	Pass	None
102	FD	AHU3.2-S12	56x16	Ruskin	IBD2	Pass	Pass	screws added
103	FD	AHU3.2-S13	8x10	Ruskin	IBD2	Pass	Pass	None
104	FD	AHU3.2-S14	56x16	Ruskin	IBD2	Pass	Pass	screws added
105	FD	AHU3.2-S15	14" oval	Ruskin	IBD2	Pass	Pass	None
106	FD	AHU3.2-S16	14" oval	Ruskin	IBD2	Pass	Pass	None
107	FD	AHU3.2-OA	96x34	Ruskin	IBD2	Pass	Pass	None
108	FD	AHU3.2-RA	96x60	Ruskin	IBD2	Pass	Pass	None

Inspector: Julie Gue
Inspection Dates: October 22, 2020 -January 20, 2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
109	FD	AHU4.1-S1	56x16	Ruskin	IBD2	Pass	Pass	screws added
110	FD	AHU4.1-S2	56x16	Ruskin	IBD2	Pass	Pass	screws added
111	FD	AHU4.1-S3	8x10	Ruskin	IBD2	Pass	Pass	None
112	FD	AHU4.1-S4	5" Round	Ruskin	IBD2	Pass	Pass	None
113	FD	AHU4.1-S5	16" Oval	Ruskin	IBD2	Pass	Pass	None
114	FD	AHU4.1-S6	56x16	Ruskin	IBD2	Pass	Pass	screws added
115	FD	AHU4.1-S7	56x16	Ruskin	IBD2	Pass	Pass	screws added
116	FD	AHU4.1-S8	8" Round	Ruskin	IBD2	Pass	Pass	None
117	FD	AHU4.1-S9	16" oval	Ruskin	IBD2	Pass	Pass	None
118	FD	AHU4.1-S10	56x16	Ruskin	IBD2	Pass	Pass	screws added
119	FD	AHU4.1-S11	8x10	Ruskin	IBD2	Pass	Pass	None
120	FD	AHU4.1-S12	56x16	Ruskin	IBD2	Pass	Pass	screws added
121	FD	AHU4.1-OA	96x24	Ruskin	IBD2	Pass	Pass	screws added
122	FD	AHU4.1-RA	96x60	Ruskin	IBD2	Pass	Pass	screws added
123	FD	AHU4.2-S1	56x16	Ruskin	IBD2	Pass	Pass	screws added
124	FD	AHU4.2-S2	56x16	Ruskin	IBD2	Pass	Pass	screws added
125	FD	AHU4.2-S3	8x10	Ruskin	IBD2	Pass	Pass	None
126	FD	AHU4.2-S4	56x16	Ruskin	IBD2	Pass	Pass	screws added
127	FD	AHU4.2-S5	16" oval	Ruskin	IBD2	Pass	Pass	None
128	FD	AHU4.2-S6	6" Round	Ruskin	IBD2	Pass	Pass	None

Inspector:

Julie Gue

Inspection Dates:

October 22, 2020 - January 20, 2021

Facility:

Virgil E Brown

SA = Supply Air

FD = Fire Damper

RA = Relief Air

EF = Exhaust Fan

OA = Outside Air

TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
 Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
21	FD	AHU1.2-S8	14x8 oval	Ruskin	IBD2	Pass	Pass	None
22	FD	AHU1.2-S9	17x8 oval	Ruskin	IBD2	Pass	Pass	None
23	FD	AHU1.2-S10	16x10	Ruskin	IBD2	Pass	Pass	None
24	FD	AHU1.2-S11	36x16	Ruskin	IBD2	Pass	Pass	None
25	FD	AHU1.2-S12	42x16	Ruskin	IBD2	Pass	Pass	None
26	FD	AHU1.2-S13	42x16	Ruskin	IBD2	Pass	Pass	None
27	FD	AHU1.2-S14	36x16	Ruskin	IBD2	Pass	Pass	None
28	FD	AHU1.2-S15	28x10	Ruskin	IBD2	Pass	Pass	None
29	FD	AHU1.2-S16	8" Round	Ruskin	IBD2	Pass	Pass	None
30	FD	AHU1.2-S17	18x10	Ruskin	IBD2	Pass	Pass	None
31	FD	AHU1.2-S18	20x8	Ruskin	IBD2	Pass	Pass	None
32	FD	AHU1.2-S19	8x10	Ruskin	IBD2	Pass	Pass	None
33	FD	AHU1.2-S20	56x16	Ruskin	IBD2	Pass	Pass	None
34	FD	AHU1.2-S21	8" Round	Ruskin	IBD2	Pass	Pass	None
35	FD	AHU1.2-OA	96x24	Ruskin	IBD2	Pass	Pass	Installed larger retaining angle
36	FD	AHU1.2-RA	96x60	Ruskin	IBD2	Pass	Pass	Installed larger retaining angle

Inspector: Julie Gue
Inspection Dates: October 22, 2020 - January 20, 2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
137	FD	AHU5.1-S1	56x18	Ruskin	IBD2	Pass	Pass	None
138	FD	AHU5.1-S2	56x18	Ruskin	IBD2	Pass	Pass	Screws added to angle
139	FD	AHU5.1-S3	36x18	Ruskin	IBD2	Pass	Pass	Screws added to angle
140	FD	AHU5.1-S4	36x18	Ruskin	IBD2	Pass	Pass	Screws added to angle
141	FD	AHU5.1-S5	56x18	Ruskin	IBD2	Pass	Pass	Screws added to angle
142	FD	AHU5.1-S6	56x18	Ruskin	IBD2	Pass	Pass	New angle and screws added
143	FD	AHU5.1-S7	8x10	Ruskin	IBD2	Pass	Pass	None
144	FD	AHU5.1-S8	8x10	Ruskin	IBD2	Pass	Pass	None
145	FD	AHU5.1-S9	10" Oval	Ruskin	IBD2	Pass	Pass	None
146	FD	AHU5.1-S10	40x10	Ruskin	IBD2	Pass	Pass	Welded Angles removed/new installed
147	FD	AHU5.1-S11	34x10	Ruskin	IBD2	Pass	Pass	Welded Angles removed/new installed
148	FD	AHU5.1-S12	10" oval	Ruskin	IBD2	Pass	Pass	None
149	FD	AHU5.1-S13	34x10	Ruskin	IBD2	Pass	Pass	Welded angles removed/new installed
150	FD	AHU5.1-OA	96x36	Ruskin	IBD2	Pass	Pass	Larger retaining angle installed
151	FD	AHU5.1-RA	96x84	Ruskin	IBD2	Pass	Pass	Larger retaining angle installed
152	FD	AHU5.2-S1	56x18	Ruskin	IBD2	Pass	Pass	None
153	FD	AHU5.2-S2	56x18	Ruskin	IBD2	Pass	Pass	None
154	FD	AHU5.2-S3	36x18	Ruskin	IBD2	Pass	Pass	Screws added to angle
155	FD	AHU5.2-S4	36x18	Ruskin	IBD2	Pass	Pass	Screws added to angle
156	FD	AHU5.2-S5	56x18	Ruskin	IBD2	Pass	Pass	Screws added to angle

Inspector:

Julie Gue

Inspection Dates:

October 22, 2020 - January 20, 2021

Facility:

Virgil E Brown

SA = Supply Air

FD = Fire Damper

RA = Relief Air

EF = Exhaust Fan

OA = Outside Air

TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
157	FD	AHU5.2-S6	56x18	Ruskin	IBD2	Pass	Pass	Screws added
158	FD	AHU5.2-S7	8x10	Ruskin	IBD2	Pass	Pass	New angle added
159	FD	AHU5.2-S8	8x10	Ruskin	IBD2	Pass	Pass	New angle added
160	FD	AHU5.2-S9	16" oval	Ruskin	IBD2	Pass	Pass	None
161	FD	AHU5.2-S10	16" oval	Ruskin	IBD2	Pass	Pass	None
162	FD	AHU5.2-S11	8" oval	Ruskin	IBD2	Pass	Pass	None
163	FD	AHU5.2-S12	44x12	Ruskin	IBD2	Pass	Pass	Welded angles removed/new installed
164	FD	AHU5.2-S13	45x10	Ruskin	IBD2	Pass	Pass	Welded angles removed/new installed
165	FD	AHU5.2-S14	8" round	Ruskin	IBD2	Pass	Pass	None
166	FD	AHU5.2-S15	16" oval	Ruskin	IBD2	Pass	Pass	None
167	FD	AHU5.2-S16	6" round	Ruskin	IBD2	Pass	Pass	None
168	FD	AHU5.2-S17	20x10	Ruskin	IBD2	Pass	Pass	None
169	FD	AHU5.2-OA	96x36	Ruskin	IBD2	Pass	Pass	Installed larger retaining angles
170	FD	AHU5.2-RA	96x84	Ruskin	IBD2	Pass	Pass	Installed larger retaining angles
171	FD	AHU5.2-S18	144x6	Ruskin	IBD2	Pass	Pass	Moved curtain into fire barrier

Inspector: Julie Gue
Inspection Dates: October 22, 2020 -January 20, 2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F:216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
172	FD	AHUG.1-S1	12" Oval	Ruskin	IBD2	Pass	Pass	None
173	FD	AHUG.1-S2	46x16	Ruskin	IBD2	Pass	Pass	None
174	FD	AHUG.1-S3	46x16	Ruskin	IBD2	Pass	Pass	None
175	FD	AHUG.1-S4	8x10	Ruskin	IBD2	Pass	Pass	None
176	FD	AHUG.1-S5	6" Round	Ruskin	IBD2	Pass	Pass	None
177	FD	AHUG.1-S6	6" Round	Ruskin	IBD2	Pass	Pass	None
178	FD	AHUG.1-S7	14" Oval	Ruskin	IBD2	Pass	Pass	None
179	FD	AHUG.1-S8	6" Round	Ruskin	IBD2	Pass	Pass	None
180	FD	AHUG.1-S9	28x10	Ruskin	IBD2	Pass	Pass	None
181	FD	AHUG.1-S10	10" Oval	Ruskin	IBD2	Pass	Pass	None
182	FD	AHUG.1-S11	5" Round	Ruskin	IBD2	Pass	Pass	None
183	FD	AHUG.1-S12	6" Round	Ruskin	IBD2	Pass	Pass	None
184	FD	AHUG.1-S13	46x16	Ruskin	IBD2	Pass	Pass	None
185	FD	AHUG.1-S14	8x10	Ruskin	IBD2	Pass	Pass	None
185	FD	AHUG.1-S15	46x16	Ruskin	IBD2	Pass	Pass	None
185	FD	AHUG.1-S16	6" Round	Ruskin	IBD2	Pass	Pass	None
185	FD	AHUG.1-OA	96x20	Ruskin	IBD2	Pass	Pass	None
185	FD	AHUG.1-RA	96x48	Ruskin	IBD2	Pass	Pass	None
186	FD	AHUG.2-S1	12" Oval	Ruskin	IBD2	Pass	Pass	None

Inspector:

Julie Gue

SA = Supply Air

FD = Fire Damper

Inspection Dates:

October 22, 2020 - January 20,2021

RA = Relief Air

EF = Exhaust Fan

Facility:

Virgil E Brown

OA = Outside Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
206	FD	AHUG.3-R1	54x18	Ruskin	IBD2	Pass	Pass	None
207	FD	AHUG.3-R2	18x16	Ruskin	IBD2	Pass	Pass	<u>None</u>
208	FD	EF7-GND	20x14	Ruskin	IBD2	Pass	Pass	Damper collecting debris
209	FD	EF7-1	22x16	Ruskin	IBD2	Pass	Pass	None
210	FD	EF7-2	26x18	Ruskin	IBD2	Pass	Pass	Damper collecting debris
211	FD	EF7-3	36x20	Ruskin	IBD2	Pass	Pass	Damper collecting debris
212	FD	EF7-4	36x20	Ruskin	IBD2	Pass	Pass	None
213	FD	EF7-5	40x20	Ruskin	IBD2	Pass	Pass	Damper collecting debris
214	FD	EF7-PH	48x18	Ruskin	IBD2	Pass	Pass	None
215	FD	EF10-GND	14x20	Ruskin	IBD2	Pass	Pass	Access door installed
216	FD	EF10-1	22x16	Ruskin	IBD2	Pass	Pass	None
217	FD	EF10-2	26x18	Ruskin	IBD2	Pass	Pass	None
218	FD	EF10-3	36x18	Ruskin	IBD2	Pass	Pass	None
219	FD	EF10-4	36x20	Ruskin	IBD2	Pass	Pass	None
220	FD	EF10-5	40x18	Ruskin	IBD2	Pass	Pass	None
221	FD	EF18-1	12x12	Ruskin	IBD2	Pass	Pass	None
222	FD	EF18-2	12x12	Ruskin	IBD2	Pass	Pass	None
223	FD	E18-3F	12x14	Ruskin	IBD2	Pass	Pass	None

Inspector:

Julie Gue

Inspection Dates:

October 22, 2020 - January 20, 2021

Facility:

Virgil E Brown

SA = Supply Air

FD = Fire Damper

RA = Relief Air

EF = Exhaust Fan

OA = Outside Air

TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
224	FD	EF18-OA	40x24	Ruskin	IBD2	Pass	Pass	None
225	FD	EF18-1	12x12	Ruskin	IBD2	Pass	Pass	None
226	FD	EF18-2	12x12	Ruskin	IBD2	Pass	Pass	None
227	FD	EF18-3	12x12	Ruskin	IBD2	Pass	Pass	None
228	FD	EF25-1	12x12	Ruskin	IBD2	Pass	Pass	None
229	FD	LL-RA-1	24x28	Ruskin	IBD2	Pass	Pass	None
230	FD	LL-RA-2	48x66	Ruskin	IBD2	Pass	Pass	None
231	FD	LL-RA-3	24x28	Ruskin	IBD2	Pass	Pass	None
232	FD	LL-RA-4	60x84	Ruskin	IBD2	Pass	Pass	None
233	FD	LL-TA-1	48x18	Ruskin	IBD2	Pass	Pass	None
234	FD	LL-TA-2	12x12	Ruskin	IBD2	Pass	Pass	None
235	FD	LL.1-S1	8x10	Ruskin	IBD2	Pass	Pass	Moved into fire barrier
236	FD	LL.1-S2	8x10	Ruskin	IBD2	Pass	Pass	Moved into fire barrier
237	FD	LL.1-OA	96x18	Ruskin	IBD2	Pass	Pass	Added larger retaining angle
238	FD	LL.1-RA	96x32	Ruskin	IBD2	Pass	Pass	Added larger retaining angle
239	FD	LL.2-S1	8x10	Ruskin	IBD2	Pass	Pass	None
240	FD	LL.2-S2	18x12	Ruskin	IBD2	Pass	Pass	None
241	FD	LL.2-S3	22x10	Ruskin	IBD2	Pass	Pass	None
242	FD	LL.2-S4	10" round	Ruskin	IBD2	Pass	Pass	none

Inspector:

Julie Gue

Inspection Dates:

October 22, 2020 - January 20, 2021

Facility:

Virgil E Brown

SA = Supply Air

FD = Fire Damper

RA = Relief Air

EF = Exhaust Fan

OA = Outside Air

TA = Transfer Air

Duct Fabricators, Inc.
 883 Addison Rd. Cleveland, Ohio
 P: 216-391-2400 F: 216-391-2492



Fire / Smoke / Fire & Smoke Damper
Composite Inspection Report

	<u>FD/SD/FSD</u>	<u>I.D.#</u>	<u>Size</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Visual</u>	<u>Functional</u>	<u>Comments</u>
243	FD	LL.2-S5	28x12	Ruskin	IBD2	Pass	Pass	None
244	FD	LL.2-S6	8x10	Ruskin	IBD2	Pass	Pass	None
245	FD	LL.2-S7	8x6	Ruskin	IBD2	Pass	Pass	None
246	FD	LL.2-OA	96x18	Ruskin	IBD2	Pass	Pass	None
247	FD	LL.2-RA	96x32	Ruskin	IBD2	Pass	Pass	None
248	FD	Dock-EA-1	30x13	Ruskin	IBD2	Pass	Pass	Npne
249	FD	Dock-EA-2	30x12	Ruskin	IBD2	Pass	Pass	New link installed
250	FD	Dock-EA-3	48x12	Ruskin	IBD2	Pass	Pass	None
251	FD	PH.1-OA	120x48	Ruskin	IBD2	Pass	Pass	Added screws to retaining angle
252	FD	PH.1-RA	108x49	Ruskin	IBD2	Pass	Pass	Added screws to retaining angle
253	FD	PH.2-OA-1	114x48	Ruskin	IBD2	Pass	Pass	None
254	FD	PH.2-OA-2	96x48	Ruskin	IBD2	Pass	Pass	None
255	FD	PH.2-OA-3	48x48	Ruskin	IBD2	Pass	Pass	None
256	FD	PH.2-RA	108x48	Ruskin	IBD2	Pass	Pass	None

Inspector: Julie Gue
Inspection Dates: October 22,2020 - January 20,2021
Facility: Virgil E Brown

SA = Supply Air FD = Fire Damper
 RA = Relief Air EF = Exhaust Fan
 OA = Outside Air TA = Transfer Air