



NOTE:

All reinforcing shall be # 4 deformed bars.
Concrete shall be ODOT class "C" #4000 PSI
in 28 days.

OPENINGS IN RISER SECTIONS for ALL pipes (Sanitary,
Combined & Storm) shall be prefabricated. Flexible
connections shall be provided for sanitary, storm and
combined sewers. Premium seals shall meet A.S.T.M
C-923.

RECTANGULAR PRECAST
CONCRETE CATCH BASIN

REVISIONS:

SCALE
NO SCALE

DATE: OCTOBER 2021